

PUMP-204 INSPECTION PROCEDURE (SYNTHETIC)

Walk-around checklist. Not a certified OEM procedure.

Before start

1. Confirm electrical isolation if a guard must be opened.
2. Look from the drive-end seal area (same view as inspection.jpg).

During run (from a safe distance)

3. Coupling guard present and bolts tight.
4. Mechanical seal: no heavy leak, steam, or burnt smell.
5. Bearing housings: unusual heat or growl.
6. Baseplate bolts and grout: no looseness or cracks.
7. Record vibration, temperature, pressure, flow, motor current.

Attention limits (demo only)

- Vibration above 7.0 mm/s
- Temperature above 70 C
- Pressure below 3.5 bar or above 6.5 bar
- Flow below 200 L/min
- Motor current above 28 A

If several limits are broken at once

Inspect seal, bearings, and suction strainer before asking for a work order.

Photograph the seal area. Save sensor_data.csv with the investigation.

This file is inspection_procedure.pdf for the INDUSAI student prototype.